BRUHAT BANGALORE MAHANAGARA PALIKE

Dasarahalli Zone, Electrical Division

19

of work :- Providing LED Street lights/Control switches/Poles/control wires at Dark/volernabal places in Ward no 13, 14 and 15

dget Head

For Rs 17469000.00

stimate No..

lo	SR Page no	Description Of Work	Unit	Qty	Rate	Amount
1	66/12.8 4	Supply of LED Streetlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate material, delivering superior light output Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, maximum light intensity should be between 60 degrees to 70 degrees CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08 Power Factor >0 9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection Compatible for pole mouting with outer dia of 40mm to 50mm Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS UL approved MCPCB Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools LED Light fixture with W System Power consumption LED Efficiency>130lm/w, nominal CRI >75 Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001 2008 Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part Warranty of 2 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED manufacturer & Cree/Nichia/ Lumileds/Osram make LED Source LED Streetlight 90 Watts	Nos	1727	7160 00	12365320 00
2	79/14 1 2	Supplying and Fixing of mm dia class A GI pipe bracket up to 2 Mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole / wall using suitable clamps, bolts and nuts and wiring using suitable capacity wires Using 32mm dia G I Pipe	Each	1727	835 00	1442045 00
3	79/14 5	Fixing halogen/metal halide / SVL / IL / LED floodlight fitting over existing pole / wall ceiling including clamps, bolts, nuts and wiring using suitable capacity	Each	1727	175 00	302225 00
4	7/2 7 1	Wiring for lighting/power circuit using one of PVC insulated 1100V grade, stranded Aluminium wire single core in open or concealed system of wiring 4	Mtrs	5000	9 00	45000 00
5	26/5 14 1	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts, necessary phase separators, handle and wiring complete Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947 (Icu = Ics) 100Amps 25kA	Each	50	4530 00	226500 00

Executive Engineer
Dasarahalli Division
Bruhat Bangalore Mahanagara Palike

Scanned by CamScanner

	6	31/5 43 2	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop In & Loop- Out terminals for 10 Sqmm / 25 Sqmm 3 5 C Al/Ar / Cu/ Ar Cable and branch out 2 5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets 260mmx210mmx116mm	Each	50	2054.00	1027[illegible]
	7	40/6 4 4	Supplying of 1 1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable as per IS-1554 (Part-1) or IS-7098 Part-1. Armouring strip thickness in average +5% and resistivity 14 Ohms/Kms (Max) as per IS-3975 4 core 16 sqmm	Mtrs	295	150.00	44250.00
	8	41/6 5 6	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required On wall /Structure 6 sqmm to 16 sqmm	Mtrs	295	30.00	8850.00
			BESCOM SR 2018-19				
	9	145/30 0/41 07	1 1 kV, LT Aerial Bunched Cable, confirming to IS-14255 1995 XLPE insulation Parameter shall be as below 1 Hot Set Test a) Elongation under Load 50% (Max) b) Permanent Elongation After Cooloing 3% (Max) 2 Thermal Aging in oven a) Tensile Strength 16 N/mm² (Min) b) Elongation 375% (Min) 3 Water Absorption Test a) Water absorbed 0 5 mg/cm² (Max) 4 Carbon Black Content shall be ranging from 2% to 3% 1x25 + 1x16 Sqmm Street light 3x25 + (Insulated Messenger cum Neutral)	Km	1.575	147000.00	231525.00
	10	224/27 0/34.04	Stringing of 1 1 kV grade Aerial Bunched 3 Core cable of XLPE insulation of size (3x95) (Phase Conductor) + (1x70) (Insulated Messenger Neutral) + (1x25) (Street Light Control)	Km	1.575	22469.00	35388.68
			Total Rs				**14803803.68**
			Add 12% GST				1776456.44
			5%Tender Premium+1%PMC Charges				888228.22
			Mislenious Charges				511.66
			Grand Total Rs				**17469000.00**

Technically sanctioned for ₹ 1,74,69,000/-

Rs. In Words: One Crore Seventy four lakhs Sixty nine thousand only

Under: Grants awaited

Job Code No: Awaited as per Comm. Order Vide no. ಮು.ಆ/ಕಾ.ಇ(93)/2021-22 Dt. 06-07-2021

Registered as EIC No. 13 / 21-22 Subject to conditions contained in Enclosed Memo No. 13 / 21-22 Dt. 5/1/22

AEE/E. TA EIC.

CERTIFICATE :-

1. The place was inspected and the work is essential.
2. The provision made in the estimate are adequate and necessary and the work comes in the BBMP limit and is legitimate Charges on the BBMP funds.
3. The estimate is based on KPWD (Ele) S R of 2019-20 &BESCOM Sr 2018-19
4. The work is not taken up in any other grants.

C.N. Babu
Assistant Engineer (Ele)
Dasarahalli Zone

ಕಾ.ಸ: 02 2022 - 2023
ದಿನಾಂಕ 12/4/2022 ರೂ.1,74,69,000/- ಅಧಿಕಾರಿಗಳ
ಅನುಮತಿ ಪತ್ರ ಅಧಿಕಾರಿಗಳು ನಿರ್ವಹಣೆ
ಪತ್ರ ಸಂಖ್ಯೆ 38 ದಿನಾಂಕ 02
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು (
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ, ಬೆಂಗಳೂರು
Executive Engineer (Ele)
Dasarahalli Zone, BBMP

Assistant Executive Engineer (Ele)
Dasarahalli Zone

Scanned by CamScanner